

Cliff Teague Restroom Building Scope of Work – December 22, 2023

1. Electrical

- a. Installation of a 200 AMP Service panel on the exterior of the building.
- b. Install occupancy light switches in the pipe chase, women's, and men's restrooms.
- c. LED lighting in pipe chase, women's, and men's restrooms.
- d. Installation of 2 LED wallpack lights at the rear and the front of the building between the 2 restrooms.
- e. Mag-locks for men's and women's restroom doors. 1200 lbs force with battery backup and programmable timer.

2. Plumbing

a. Install commercial flush valve toilets in both restrooms if possible. This may not be possible due to the supply line being 3/4".

3. Doors

- a. Remove and install two new metal doors and frames for men's and women's restrooms.
- b. Paint three exterior and interior doors and frames.
- c. Key 3 doors to our key system with 2 needed mag locks.
- d. Door closures on men's and women's doors.

4. Exterior Building

- a. Pressure wash building and concrete pad.
- b. Paint four walls and concrete roof.
- c. Install rock veneer with water table/ledger (ex. Palos Verde Stone) 3' high around building.

5. Interior Restrooms

- a. Paint men's and women's restroom walls and epoxy floors.
- 6. Demolition debris is to be disposed of offsite.